Souto Bros.
15934 Hesperian Blvd. #126
San Lorenzo, CA 94580

Landscape contract

DATE	CONTRACT ...
4/25/2012	859

NAME / ADDRESS
San Leandro Unified School District Attn: Greg Dyer 1145 Aladdin Ave San Leandro, CA 94577

P.O. NO.	TERMS	REP	PROJECT	JOB #
	See Terms Below	DS	James Monroe Elem...	

DESCRIPTION	TOTAL
JAMES MONROE ELEMENTARY SCHOOL ASPHALT PROJECT DEMO: This work includes to remove (2) large tree with tree roots, and (2) stump with a stump grinder. Saw cut approximately 40 linear ft. of existing asphalt. Jackhammer and remove 24' x 24' of existing asphalt. Remove 4" of existing soil. Dispose of all debris. ASPHALT: This work includes installation of 3" - 4" base rock (compacted) for 24' x 24' asphalt area. Installation of 24 linear ft. of 2" x 4" redwood header board. Oil all edges as necessary. Installation of 24' x 24' of 1/2" fines asphalt, 3" thick. Roll and compact with 36" vibratory roller. BLUE FINES: This work includes to excavate soil, 4" deep for 8' x 16' area. Installation of crushed granite blue fines, 4" deep. Compact with a vibrator plate. PLANTINGS: This work includes to plant (2) 24" Box Chinese Pistache in designated areas. Installation of stakes, and straps. CHAIN LINK FENCE: This work includes installation of 40' long x 4' high chain link fence. Posts to be set in concrete. Clean area at completion. NOTE: This is a prevailing wage project	14,966.00

Thank you for giving us the opportunity to serve you.	**TOTAL**

SIGNATURE _____

Phone #	Fax #	E-mail	Web Site
510-581-4172	510-581-4172	davidsouto@comcast.net	www.soutobros.com