LEMKE LANDSCAPE
CHRISTOPHER R. LEMKE
Landscape Contractor Lic #751366

14677 Merced Street, San Leandro, CA 94579
(510) 895-1714 PH & FX

Estimate

DATE	ESTIMATE NO.
2/2/2013	370

NAME / ADDRESS

San Leandro Unified School District
Maintenance Department
1145 Aladdin Avenue
San Leandro, CA 94577

PROJECT

DESCRIPTION	QTY	COST	TOTAL
Landscape Installation at McKinley School Demo existing garden area in front of school along east 14th St. Leaving sidewalk inplace, (Chain link fencing, shed, planter boxes, pavers, misc debris) Rototill soils and add amendments and new soils to bring to grade and prep for sod install Irrigation renovations using existing valves and lateral irrigation lines, add as needed install pvc and Rainbird 5000 and 3500 series rotor heads to cover new sod and minimize over-spray on sidewalk. if existing system is not adequate then additional charges will apply to upgrade Prepare final grade for sod installation and install new sod	1	18,194.40	18,194.40

Please sign and fax or e-mail back if acceptable

TOTAL $18,194.40