East Bay
RESTAURANT SUPPLY INC.

Quote

05/27/2021

To:
San Leandro Unified Food Services
1193 Aladdin Ave
San Leandro, CA 94577

Project:
Bandroft Middle School
San Leandro, CA 94577

From:
East Bay Restaurant Supply, Inc.
Carlito Oyas
49 Fourth Street
Oakland, CA 94607-4603
(510) 465-4300
(510)465-4300 (Contact)

Project Code: 70679 Job Reference Number: 66334

Item	Qty	Description	Sell	Sell Total
1	1 ea	**KETTLE, GAS, TILTING**	$25,250.00	$25,250.00
		Cleveland Range Model No. KGL60T Kettle, gas, tilting, 60-gallon capacity, 2/3 steam jacket design, with floor mounted control console supports, 316 series stainless steel interior, flanged feet, 50 psi rating, electronic spark ignition, cover & draw-off optional, 190,000 BTU Dimensions 48.13(h) x 49.38(w) x 47.25(d)		
	1 ea	1-year parts & labor warranty, standard		
	1 ea	Extended Warranty, not to exceed 36 months from date of installation (K-12 Schools only)		
	1 ea	10-Year Hemispheric Bottom Warranty (K-12 Schools only)		
	1 ea	Performance start-up included at customer request after equipment is installed (Free Water Quality Check included) (contact Cleveland Sales Representative for details)		
	1 ea	Natural Gas		
	1 ea	120v/60/1-ph, 10.0 amps, electronic spark ignition, cord & plug for controls, standard		
	1 ea	Standard controls, temperature control dial, LED ON indicator light, main power switch with standard and high power setting, standard		
	1 ea	TD2A45 2" tangent draw-off valve with ACME thread, 45° elbow, 8' length of 2" ID hose, hose clamp	$895.00	<Optional>
	1 ea	NOTE: TD2A must be configured on kettle at time of purchase. It cannot be replaced, installed or retrofitted in the field.		
	1 ea	CHS60 Spring-assisted cover (60 gallon)	$1,210.00	<Optional>
	1 ea	DKFK Double Pantry Kettle Filler, with 60" hose	$957.41	<Optional>
	1 ea	FBKT Faucet Bracket (required for mounting faucet)	$180.02	<Optional>
	Class 85	Weight: 600.5 lbs total		
			ITEM TOTAL:	**$25,250.00**
2	2 ea	**COMBI OVEN, GAS**	$15,610.00	$31,220.00

Initial: _____

Item	Qty	Description	Sell	Sell Total
		Angelo Po America Model No. FX82G3T CombiStar™ Combi Oven, gas, boilerless, (16) 12" x 20" full size hotel or (8) 18" x 26" full size sheet pan capacity, programmable controls, touch display, (150) cooking programs with favorites menu, USB interface, automatic venting, humidity sensor, auto-reversible 6-speed fan, multi-point core temperature probe, double-glazed door with window, fully-automatic cleaning system with (1) rinse & (1) detergent chemicals, (LDR610) retractable spray gun, stainless steel construction, instructional training, 92,500 BTU, IPX5, NSF, cETLus Dimensions 36.81(h) x 46.38(w) x 42.91(d)		
	2 ea	Initial Site Checklist-Must be submitted with PO. If purchasing Certified installation, product will not ship until checklist is received by Angelo Po. 30% restocking fee for returned merchandise declining Certified Installation if checklist has not been signed		
	2 ea	Gas type to be specified		
	2 ea	120v/60/1-ph, 0.9 kW, 7.8 amps, AWG12, standard		
	2 ea	One Year Warranty - parts and labor - standard from date of installation or eighteen (18) months after shipping date (whichever occurs first)		
	2 ea	Certified Installation and Start-Up of combi oven, for FX61, FX101, FX82, FX122 ovens. Includes preliminary site visit within 50 miles (100 miles round trip) from installer. (NET) Includes installation of APRO reverse osmosis system if ordered, but does not include APRO reverse osmosis system. Does not include FXGIK installation kit Order APRO system and FXGIK kit separately	$1,335.00	$2,670.00
	2 ea	On site Chef Training [included with Certified Installation] Includes: *One 2 hour instructional training by local MAFSI rep after start up to address all basic oven operation questions as scheduled by owner or operator *One 4-hour Certified Chef training 21 days after initial rep training to address detailed and more specialized menu-specific questions as scheduled by owner and operator		
	2 ea	FXGIK Gas Installation Kit, for all FX series gas ovens (NET) Kit includes: (20) feet of 1-1/2" CPVC pipe (2) 1-1/4" rubber coupling (2) 1-1/4" 90° CPVC fitting	$554.95	$1,109.90

Initial: _____

Item	Qty	Description	Sell	Sell Total
		(1) 1-1/4" 45° CPVC fitting (1) can CPVC cement (1) Dormont 3/4" x 48" gas hose kit (1) 14/3 power cord (1) 14/3 cord restraint		
	1 ea	APRO Wall Mount Reverse Osmosis Water Treatment System, 500 gpd, sediment, for chlorine taste & odor, chloramines, hardness & TDS reduction, dual outlet feeds (water cycle & wash cycle), wall mount system including 2-gallon RO reserve tank, non-electric permeate pump, quick change prefilters and RO membrane cartridge, for use on all APA combi ovens [no copper piping between RO system and oven] (NET)	$1,407.56	$1,407.56
	2 ea	Door hinged on right, standard		
	1 ea	KSFX82G Stacking kit, gas or electric oven on top of a gas oven (NET)	$1,343.99	$1,343.99
	1 ea	TRKSFX82 Support frame with casters, for use when stacking FX82/FX82 (increases overall height dimension 4”)	$990.95	$990.95
	1 ea	AP Flat Rate Freight - please select freight zone below		
	1 ea	Double stacked units (two ovens) for FX82 are same freight price as a single oven		
	1 ea	Zone 6: FX82/FX122/FX201/FX202 - AZ, UT, NV, CA, OR, WA, ID, MT	$903.06	$903.06
	2 ea	Important Notes: 1. Water must meet minimum specified quality standards (see spec sheet) or appropriate filtration will be required. Pressure: WITH Angelo Po RO System= 50-125psi; WITHOUT RO= 30-60psi 2. Drain Cannot be located directly under combi oven 3. Chemicals- Please allow location for chemicals when ordering double stacked ovens 4. Electrical- No GFCI plugs on gas ovens. Local code may require a service disconnect on electrical seal tight conduit (provided by licensed electrician) 5. RO System- Pre-determine wall mounting location when choosing optional RO system, maximum 15ft. from oven		
	Class 85	Weight: 1160 lbs total		
			ITEM TOTAL:	**$39,645.46**
3	2 ea	**COMBI OVEN, ELECTRIC**	$12,880.04	$25,760.08

Initial: _____

Item	Qty	Description	Sell	Sell Total
		Angelo Po America Model No. FX82E3T CombiStar™ Combi Oven, electric, boilerless, (16) 12" x 20" hotel pans or (8) 18" x 26" full size sheet pan capacity, programmable controls with touch display, (150) cooking programs with favorites menu, USB interface, automatic venting, humidity sensor, auto-reversible 6-speed fan, multi-point core temperature probe, double-glazed door with window, fully-automatic cleaning system with (1) rinse & (1) detergent chemicals, (LDR610) retractable spray gun, stainless steel construction, instructional training, IPX5, NSF, cETLus Dimensions 36.81(h) x 46.38(w) x 42.91(d)		
	2 ea	Initial Site Checklist-Must be submitted with PO. If purchasing Certified installation, product will not ship until checklist is received by Angelo Po. 30% restocking fee for returned merchandise declining Certified Installation if checklist has not been signed		
	2 ea	208v/60/3-ph, 20.7 kW, 57.5 amps, AWG8, standard		
	2 ea	Note: Electric Supply Connectors are not provided and are the customer's responsibility		
	2 ea	One Year Warranty - parts and labor - standard from date of installation or eighteen (18) months after shipping date (whichever occurs first)		
	2 ea	K-12 2nd Year Warranty - parts and labor - (Must purchase Certified Installation, RO & Install Kit)		
	2 ea	Certified Installation and Start-Up of combi oven, for FX61, FX101, FX82, FX122 ovens. Includes preliminary site visit within 50 miles (100 miles round trip) from installer. (NET) Includes installation of APRO reverse osmosis system if ordered, but does not include APRO reverse osmosis system. Does not include FXEIK installation kit Order APRO system and FXEIK kit separately	$1,336.93	$2,673.86
	2 ea	On site Chef Training [included with Certified Installation] Includes: *One 2 hour instructional training by local MAFSI rep after start up to address all basic oven operation questions as scheduled by owner or operator *One 4-hour Certified Chef training 21 days after initial rep training to address detailed and more specialized menu-specific questions as scheduled by owner and operator		
	2 ea	FXEIK Electric Installation Kit, for all FX series electric ovens (NET) Kit includes:	$327.93	$655.86

East Bay
RESTAURANT SUPPLY INC.

Item	Qty	Description	Sell	Sell Total
		(20) feet of CPVC pipe (2) 1-1/4" rubber couplings (2) 1-1/4" 90° CPVC fittings (1) 1-1/4" 45° CPVC fitting (1) can CPVC cement		
	1 ea	APRO Wall Mount Reverse Osmosis Water Treatment System, 500 gpd, sediment, for chlorine taste & odor, chloramines, hardness & TDS reduction, dual outlet feeds (water cycle & wash cycle), wall mount system including 2-gallon RO reserve tank, non-electric permeate pump, quick change prefilters and RO membrane cartridge, for use on all APA combi ovens [no copper piping between RO system and oven] (NET)	$1,407.56	$1,407.56
	2 ea	Door hinged on right, standard		
	1 ea	KSFX82G Stacking kit, gas or electric oven on top of a gas oven (NET)	$1,343.99	$1,343.99
	1 ea	TRKSFX82 Support frame with casters, for use when stacking FX82/FX82 (increases overall height dimension 4”)	$990.95	$990.95
	1 ea	AP Flat Rate Freight - please select freight zone below		
	1 ea	Zone 6: FX82/FX122/FX201/FX202 - AZ, UT, NV, CA, OR, WA, ID, MT	$903.06	$903.06
	1 ea	Important Notes: 1. Water must meet minimum specified quality standards (see spec sheet) or appropriate filtration will be required. Pressure: WITH Angelo Po RO System= 50-125psi; WITHOUT RO= 30-60psi 2. Drain Cannot be located directly under combi oven 3. Chemicals- Please allow location for chemicals when ordering double stacked ovens 4. Electrical- No GFCI plugs on gas ovens. Local code may require a service disconnect on electrical seal tight conduit (provided by licensed electrician) 5. RO System- Pre-determine wall mounting location when choosing optional RO system, maximum 15ft. from oven		
Class 85		Weight: 1094 lbs total		

ITEM TOTAL:	**$33,735.36**
Merchandise	$98,630.82
Tax 9.75%	$9,616.50
Total	$108,247.32

Prices Good Until: 06/28/2021

Initial: _____

East Bay
RESTAURANT SUPPLY INC.

Acceptance: _____ Date: _____

Printed Name: _____